BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2014-15/OW/WORK_INDENT14636

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/07/2014-15, Date: 31.10.2014

Providing Emergency and Maintanance works in ward no 07 Byatarayanapura

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of PRATAP	
				In Figures	In Words
1	142.56	buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods	cum	174.27	Rupees One Hundred Seventy Four and Twenty Seven Paise Only
2	23.76	KSRB 4-1.2: Providing and laying in position plain cement concrete of I mix M10 With OPC cement @ 220 Kgs with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P. 12, I.No. 4.2) SR-2014-15	cum	5013.47	Rupees Five Thousand Thirteen and Forty Seven Paise Only
3	31.68	KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 (P. 23, I.No. 5.6) SR-2014-15	Sqm	3797.79	Rupees Three Thousand Seven Hundred Ninety Seven and Seventy Nine Paise Only
4	77.59	KSRB 4-6.1 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specificaitons.	cum	234.15	Rupees Two Hundred Thirty Four and Fifteen Paise Only
5	167.52	KProviding and laying cement concrete using 20mm and down size granite jelly of ready mix concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., including smooth finish in CM 1:3, with all lead and lift etc., complete. (exculsive of cost of steel, fabrication and plastering charges)Ready mixed Cement concrete for Beams, Columns, Staircase and Roof with M-20 (1:1.5:3) (Cement-3320Kg/cum) (P. 18, I.No. 4.49.1) SR-2014-15	cum	5788.64	Rupees Five Thousand Seven Hundred Eighty Eight and Sixty Four Paise Only
6	8.6	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. (P. 19, I.No. 4.46) SR-2014-15	Qtl	77568.32	Rupees Seventy Seven Thousand Five Hundred Sixty Eight and Thirty Two Paise Only
7	52.8	KSRB 15.1.3 – do – Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. (P.109.I.No. 15.3) SR-2014-15	Sqm	90.88	Rupees Ninety and Eighty Eight Paise Only

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore-92

8	869.88	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 5.00 Km (Page No.141)	cum	80.19	Rupees Eighty and Nineteen Paise Only
9	142	Providing JCB Per DAY Pg no : xxxxvi i.no : 23 PWD SR 2014-15	Days	6652.8	Rupees Six Thousand Six Hundred Fifty Two and Eighty Paise Only
10	140	Engaging Tracter 50HP Pg no : xxxxvii, i.no : 38 PWD SR 2014-15	Days	2217.6	Rupees Two Thousand Two Hundred Seventeen and Sixty Paise Only
11	800	Engaing of Labour Pg no L1V, i.no : 5 PWD SR 2014-15	Days	221.69	Rupees Two Hundred Twenty One and Sixty Nine Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92